

# American Public Works Association New Mexico Chapter Modified Section 802: Installation of Water Service Lines

These Standards amend or supplement the American Public Works Association New Mexico Chapter (NMAPWA) Current Edition as indicated below in red. All sections, which are not so amended or supplemented, remain in full force and effect.

802.1 GENERAL: This section pertains to the water service line which extends from the distribution line to the water meter.

802.2 REFERENCES:

802.2.1 American Society for Testing and Materials (ASTM) (Latest Edition):

A48 Specification for Gray Iron Castings

B62 Specification for Composition Bronze or Ounce Metal Castings

B88 Specification for Seamless Copper Water Tube

D2000 Classification System for Rubber Products in Automotive Applications

802.2.2 American Water Works Association (AWWA) (Latest Edition):

C800 Underground Service Line Valves and Fittings

802.3 MATERIALS:

Delete Section 802.3.1 in its entirety and substitute the following:

802.3.1 SERVICE LINE FITTINGS: All service line fittings shall be in full compliance with the latest revision of AWWA Standard C800, except as modified herein. Service line fittings will be of brass which comply with the U.S. Federal Reduction of Lead in Drinking Water Act of 2011 with all applicable amendments since that date. Fittings will be of the type required for the type of service line being installed. All stops shall be of the round, full opening type with no restriction in the opening less than the nominal size. Fittings incorporating a threaded plastic gripper and "O" ring seal may be utilized in lieu of the flared configuration. All service pipe

and fittings shall be designed to sustain and operating pressure of 150 psi.

802.3.2 COPPER SERVICE PIPE: The 3/4" to 2" copper service pipe shall conform to ASTM B88 and shall be Type K, unless otherwise specified. Copper tubing shall be bent with approved tube benders without any kinks or sharp bends. Cutting of tubing will be performed with cutters designed for that purpose.

802.3.3 TAPPING SADDLES:

802.3.3.1 Service saddle bodies shall be of cast iron, ductile iron or bronze; straps, nuts, bolts, and washers shall be of stainless steel or bronze; gaskets shall be vulcanized elastomeric rubber or synthetic rubber compound.

802.3.3.2 The saddles shall be tapped for the type of thread being used on the corporation stop.

802.3.3.3 Tapping saddles for PVC C900 pipe shall have bronze straps and shall be installed as per the manufacturer's printed recommendations.

802.3.4 METERS: Meters are furnished and installed by OWNER for new service line installations. For replacement and relocation work the meters will be furnished by the OWNER and installed by the CONTRACTOR.

Delete Section 802.3.5 and its subsections in its entirety and substitute the following:

802.3.5 METERS:

802.3.5.1 METER BOXES FOR 3/4"-1" METERS:

802.3.5.1.1 Meter boxes with two meters shall be centered on adjacent property lines.

802.3.5.1.2 The meter box is to be part of an underground enclosure for water meters and will have a cast iron cover plate or lid.

802.3.5.1.3 Meter box will be cast in one piece to form a hollow rectangle and new material or recycled materials shall be used in its manufacture.

# American Public Works Association New Mexico Chapter

## Modified Section 802: Installation of Water Service Lines

802.3.5.1.4 The box material shall have the following minimum mechanical properties at variable ambient temperatures of -20 F to 120 F: compressive strength = 10,000 psi, tensile strength = 1,500 psi and flexural strength = 7,500 psi.

802.3.5.1.5 During testing of the materials at the above ambient temperatures no visual cracking, crazing, checking, blistering, surface pitting or deformation will be noted.

802.3.5.1.6 The finished meter box shall have the following physical properties:

802.3.5.1.6.1 Maximum wall deflection shall not exceed 1/8" at any one point when subjected to earth pressures or forces created during backfilling.

802.3.5.1.6.2 Material used for making the box shall be non-biodegradable when buried and/or exposed to water. Life expectancy of the box shall be at least 20 years.

802.3.5.1.6.3 Overall weight of the box component shall not exceed 80 pounds.

802.3.5.1.6.4 Inside dimensions of the box shall be: width = 16 1/2 inches, length = 22 1/2 inches, and depth = 24 inches. See Standard Detail Drawings for further dimensions and configurations. This meter box is for one and two meter installations.

802.3.5.1.6.5 Inside and outside surfaces of walls shall be reasonable smooth and free of burrs.

802.3.5.1.6.6 All materials used for box construction shall be approved for use in domestic water supply system.

### 802.3.5.2 METER BOXES FOR 1" AND SMALLER METERS:

802.3.5.2.1 MATERIALS: The meter box shall be designed to withstand loading in non-deliberate and incidental traffic and are not to be installed in roadway. The meter box shall be black and constructed of modified polyethylene material for maximum durability and corrosion

resistance. The black material is for maximum ultraviolet protection. The black material shall be uniform throughout the meter box for maximum longevity and not have a foaming agent that creates air pockets within the plastic wall.

### 802.3.5.2.2 VERTICAL AND LATER LOAD RATING:

802.3.5.2.2.1 The meter box shall be compliant with American Association of State Highway and Transportation Officials, design load of H-10; American Society for Testing and Materials Standard C857-95, design load of A-8, 8,000 lbs., transferred through a 10" by 10" steel plate centered in the cover and body.

802.3.5.2.2.2 The meter box shall be compliant with American Association of State Highway and Transportation Officials, design load of H-20; American Society for Testing and Materials Standard C857-95, design load of A-16, 16,000 lbs., transferred through a 10" by 20" steel plate centered in the cover and body.

802.3.5.2.2.3 The meter box shall be designed to withstand H-10 and H-20 loading in non-deliberate or incidental traffic areas. The meter box is not intended to be installed in roadways.

### 802.3.5.2.3 POLYMER AMR/AMI LID WITH REBAR:

802.3.5.2.3.1 The polymer lid shall be solid through with two 1/2" rebar molded in lid for locatability.

802.3.5.2.3.2 The polymer lid shall have a molded key hole and molded lock options underneath lid for placement of optional security locking mechanism.

802.3.5.2.3.3 The polymer lid shall seat securely and evenly inside the meter box and shall not overlap the top edge of the meter box.

802.3.5.2.3.4 The polymer lid shall have two molded slide mount brackets for placement of automatic meter reading/automatic meter infrastructure device.

# American Public Works Association New Mexico Chapter

## Modified Section 802: Installation of Water Service Lines

802.3.5.2.3.5 The polymer lid shall have molded tread-pattern for skid resistance-tread dimensions shall be 0.188" by 0.938" by 0.150" deep.

802.3.5.2.3.6 The polymer lid shall have "WATER METER" molded into the lid-font shall be standard computer-numerical-control font with 1" characters by 0.150" deep.

802.3.5.2.3.7 The polymer lid shall retrofit existing concrete meter boxes with similar dimensions and be able to adjust in the field.

802.3.5.2.3.8 The polymer lid shall be recycled with a minimum of 50% post-consumer recycled and 50% postindustrial/pre-consumer recycled content-verified with a LEED product certification marking.

### 802.3.5.2.4 POLYMER BODY:

802.3.5.2.4.1 The polymer body shall be black and have a minimum 3/8" wall thickness.

802.3.5.2.4.2 The two polymer bodies shall be bolted and sealed together to form one unit at 26" deep.

802.3.5.2.4.3 The polymer body shall have a minimum inside working area of 19-1/2" by 16-1/2".

802.3.5.2.4.4 The polymer body shall have crush resistant ribbing along the outside of the box.

802.3.5.2.4.5 The polymer body shall have a flange around the lid opening to help prevent settling and aide in the adjustment to grade.

802.3.5.2.4.6 The polymer body shall have one pipe slot cut out on one end and two on other side of the body that measure 3" by 4".

802.3.5.2.4.7 The polymer body shall be recycled with a minimum of 35% postindustrial/pre-consumer recycled content-verified with a LEED product certification marking.

Delete Section 802.3.5.3 and its subsections in its entirety and substitute the following:

### 802.3.5.3 METER BOXES FOR 1 1/2" AND 2" METERS:

802.3.5.3.1 MATERIALS: The meter box shall be designed to withstand loading in non-deliberate and incidental traffic and are not to be installed in roadway. The meter box shall be black and constructed of modified polyethylene material for maximum durability and corrosion resistance. The black material is for maximum ultraviolet protection. The black material shall be uniform throughout the meter box for maximum longevity and not have a foaming agent that creates air pockets within the plastic wall.

### 802.3.5.3.2 VERTICAL AND LATER LOAD RATING:

802.3.5.3.2.1 The meter box shall be compliant with American Association of State Highway and Transportation Officials, design load of H-10; American Society for Testing and Materials Standard C857-95, design load of A-8, 8,000 lbs., transferred through a 10" by 10" steel plate centered in the cover and body.

802.3.5.3.2.2 The meter box shall be compliant with American Association of State Highway and Transportation Officials, design load of H-20; American Society for Testing and Materials Standard C857-95, design load of A-16, 16,000 lbs., transferred through a 10" by 20" steel plate centered in the cover and body.

802.3.5.3.2.3 The meter box shall be designed to withstand H-10 and H-20 loading in non-deliberate or incidental traffic areas. The meter box is not intended to be installed in roadways.

### 802.3.5.3.3 POLYMER AMR/AMI LID WITH REBAR:

802.3.5.3.3.1 The polymer lid shall be solid through with two 1/2" rebar molded in lid for locatability.

# American Public Works Association New Mexico Chapter

## Modified Section 802: Installation of Water Service Lines

802.3.5.3.3.2 The polymer lid shall have a molded key hole and molded lock options underneath lid for placement of optional security locking mechanism.

802.3.5.3.3.3 The polymer lid shall seat securely and evenly inside the meter box and shall not overlap the top edge of the meter box.

802.3.5.3.3.4 The polymer lid shall have two molded slide mount brackets for placement of automatic meter reading/automatic meter infrastructure device.

802.3.5.3.3.5 The polymer lid shall have molded tread-pattern for skid resistance-tread dimensions shall be 0.188" by 0.938" by 0.150" deep.

802.3.5.3.3.6 The polymer lid shall have "WATER METER" molded into the lid-font shall be standard computer-numerical-control font with 1" characters by 0.150" deep.

802.3.5.3.3.7 The polymer lid shall retrofit existing concrete meter boxes with similar dimensions and be able to adjust in the field.

802.3.5.3.3.8 The polymer lid shall be recycled with a minimum of 50% post-consumer recycled and 50% postindustrial/pre-consumer recycled content-verified with a LEED product certification marking.

### 802.3.5.3.4 POLYMER BODY:

802.3.5.3.4.1 The polymer body shall be black and have a minimum 3/8" wall thickness.

802.3.5.3.4.2 The two polymer bodies shall be bolted and sealed together to form one unit at 26" deep.

802.3.5.3.4.3 The polymer body shall have a minimum inside working area of 16 5/16" by 31 3/4".

802.3.5.3.4.4 The polymer body shall have crush resistant ribbing along the outside of the box.

802.3.5.3.4.5 The polymer body shall have a flange around the lid opening to help prevent settling and aide in the adjustment to grade.

802.3.5.3.4.6 The polymer body shall have one pipe slot cut out on one end and two on other side of the body that measure 3" by 4".

802.3.5.3.4.7 The polymer body shall be recycled with a minimum of 35% postindustrial/pre-consumer recycled content-verified with a LEED product certification marking.

802.3.5.4 LOCATIONS OF METER BOXES: Meter Boxes shall be located within the right-of-way as shown on Standard Detail Drawings.

802.3.6 CORPORATION STOP: Corporation stop shall be AWWA thread inlet by compression-type outlet or Pack Joint to fit 3/4", 1", 1 1/2" and 2" copper tubing. The socket-housing or the rotating ball shall be PTFE coated to avoid metal to metal contact, ensure adequate seal and provide smooth turning operation. Outlet shall have a nominal size Standard AWWA C800 copper service thread to fit existing OWNER drilling and tapping machine equipment. All casting shall be ASTM B62 and outlet seals shall be Buna-N.

802.3.7 TAILPIECE: The service will be placed in the meter box with a copper tubing tailpiece for 3/4" to 2", protruding from the standard concrete pad into the owner's property with a Pack Joint capped fitting to which the plumber can connect.

802.3.8 COPPERSETTERS: Coppersettors shall have pipe connections for Type K Copper Tubing. The coppersetter shall be an assembly of brass and copper tubing with a bottom bar, shall have a bronze ball valve on the inlet side of the meter, and shall be furnished with coupling gaskets. Coppersettors shall have temporary threaded plugs in the meter connections and shall be furnished free of excess grease. A stabilizer bar of 12 inches by 1/2 inch galvanized pipe shall be inserted in the yoke assembly as shown on the Standard Detail Drawings. A coppersetter with dual check valve shall be installed as per the Cross Connection Control section.

# American Public Works Association New Mexico Chapter

## Modified Section 802: Installation of Water Service Lines

### 802.3.9 CROSS CONNECTION CONTROL:

Approved dual check valves shall be installed on all services as indicated on the plans. For water customers having private wells located that connect to the municipal water system shall agree to completely sever the private well from the premises existing plumbing system and install an approved dual check valve at the water meter. The owner of the premises shall also sign a covenant that runs with the land that the private well shall not be reconnected to the premises previous plumbing.

### 802.4 SERVICE LINE INSTALLATION:

#### 802.4.1 NEW 3/4" TO 2" SERVICE LINES:

802.4.1.1 New Service lines are complete new services in accordance with Standard Detail Drawings and shall include the following:

802.4.1.1.1 Furnish and install tapping saddle, corporation stop, tubing, coppersetter, meter box, cover and lid and tailpiece, complete in place, including excavation and backfill and flushing.

802.4.1.2 Meters will not be installed as part of this work. However, construction of the meter box and placement of the yoke shall be such that at a later date the meter may be installed properly and easily.

802.4.1.3 The CONTRACTOR shall be responsible for proper vertical and horizontal location of the box over the meter yoke.

#### 802.4.2 REPLACEMENT 3/4"-2" SERVICE LINES:

802.4.2.1 Replacement service lines are essentially new services installed in conjunction with the replacement of the water main. Unless otherwise specified in the Contract Documents, all existing services shall be replaced with new material between the water main and the meter yoke.

802.4.2.2 Replacement service line work does not include any relocation or rehabilitation of the meter. The work shall consist of the following:

802.4.2.2.1 Furnish and install tapping saddle, corporation stop, coppersetter and tubing, complete in place, including flushing.

802.4.2.2.2 Re-connection to the meter.

802.4.2.2.3 All necessary excavation and backfill and concrete removal and replacement.

#### 802.4.3 3/4" THRU 2" METER RELOCATION:

802.4.3.1 A meter relocation is the relocation of an existing meter to a position closer to or further away from the centerline of the street. The meter relocation item is to be used when the service line is not replaced.

802.4.3.2 A new meter box and cover shall be furnished and installed.

802.4.3.3 A coppersetter shall be used in the reinstallation of the meter, for services sized 3/4" thru 2", and shall be of a height to properly position the meter, vertically, within the box, as shown in the Standard Detail Drawings.

802.4.3.4 When moving the meter toward the property line, new tubing shall be installed, from the inlet connection point of the meter to be relocated, to the coppersetter, and a tailpiece shall be installed on the outlet side of the coppersetter to the property line. When the existing meter is moved toward the street, the gap in the service line shall be filled with new tubing, including connectors.

802.4.3.5 When determined by the OWNER, the existing meter shall be replaced by the CONTRACTOR with a meter furnished by the OWNER. 1" meters will be substituted for 1-1/4" meters.

802.4.3.6 The work and materials shall include the coppersetter, connector pieces, excavation, tubing, backfill, removal of old meter and meter box, installation of new meter, meter box, and concrete pad, necessary disconnections, and connections of the house and meter box service lines, complete restoration of the affected site (including landscaping) and adjustment of the meter to the level shown in the Standard Detail Drawings.

# American Public Works Association New Mexico Chapter

## Modified Section 802: Installation of Water Service Lines

### Add the following:

#### 802.5 RESERVED.

#### 802.6 3/4" THRU 2" METER REHABILITATION AND REPLACEMENT:

##### 802.6.1 3/4" THRU 2" METER REHABILITATION:

802.6.1.1 Meter rehabilitation is applicable where the meter box deficiency exists. Deficiencies include obsolete, broken above or below grade, improperly sized, or existing location does not allow access to the meter, curb stop or connector pieces (does not meet new installation standards). When any of these conditions exists, the meter box and meter installation shall be rehabilitated, as authorized by the ENGINEER.

802.6.1.2 The work and materials shall include:

802.6.1.2.1 Furnish and install a new coppersetter, meter box, cover and lid and concrete pad.

802.6.1.2.2 Furnish and install any reconnection pieces necessary for a complete service restoration.

802.6.1.2.3 Flushing out of the service line.

802.6.1.2.4 Site restoration (including any necessary landscaping) and cleanup.

802.6.2 3/4" THRU 2" METER REPLACEMENT: Meters to be replaced under "Service Line Replacement" and "Meter Relocation" work shall be performed in accordance with the following procedure:

802.6.2.1 All existing meters involved with "Service Line Replacement" and "Meter Relocation" work shall be replaced by the CONTRACTOR with a meter provided by the OWNER as determined by the OWNER.

802.6.2.2 The replacement meter shall be requested, in writing by the CONTRACTOR from the OWNER with documentation of address and size meter for each meter to be replaced, project name and number, and CONTRACTOR's name.

802.6.2.3 The request shall be received at least seven days prior to issuance of meters.

802.6.2.4 The CONTRACTOR will be issued a directive with each meter issued. The CONTRACTOR shall return the directive along with the replaced meter, within five days of replacement of the meter to the OWNER.

802.6.2.5 The work order must be turned in with the specific meter for which the meter replacement was issued. The replaced meter shall have a tag affixed to the meter, by the CONTRACTOR, showing the CONTRACTOR's name, and project name and address from which the meter was removed.

802.6.2.6 The CONTRACTOR shall handle all meters so as not to damage them and shall be responsible for the meters from the time of receipt to turn in. Stolen or lost meters shall be replaced at the CONTRACTOR's expense.

802.7 METER PIT FOR SERVICES 3" AND LARGER: Meter pit construction details and the installation of the pipe, valves and meter details will be shown on the construction plans.

#### 802.8 MEASUREMENT AND PAYMENT:

802.8.1 METERED SERVICE LINE INSTALLATIONS: For 3/4-inch thru 2-inch, new service lines, service line replacements and transfers, meter relocations, and meter replacements, and meter rehabilitation shall be measured and paid for as a completed unit of installation in accordance with the applicable items contained in the Bid Proposal, which payment shall include all materials, labor and equipment required to install, flush and place into service the applicable item.

802.8.2 SERVICE LINE TUBING: Unless otherwise authorized in the Contract Documents or by the ENGINEER, service line tubing shall be considered incidental to the applicable pay item established in the Bid Proposal.

# **American Public Works Association New Mexico Chapter Modified Section 802: Installation of Water Service Lines**

802.8.3 PAVEMENT REMOVAL AND REPLACEMENT: Unless otherwise authorized in the Contract Documents or by the ENGINEER, pavement removal and replacement shall be considered incidental to the applicable pay item established in the Bid Proposal.